

Prompt 1 — Phase 1 brief (verbatim, as issued by Shahbaz Ahmed)

Attached file: `Disrupt\_Architectural Working set \_060326.pdf` (23 pages)

ROLE: SENIOR ARCHITECTURAL VISUALIZER, BIM MODELLER,
ARCHITECTURAL COORDINATION ENGINEER & PHOTOREALISTIC
3D ENVIRONMENT ARTIST

PROJECT:

DISRUPT — ARCHITECTURAL 3D VISUALIZATION

REFERENCE FILE:

Disrupt_Architectural Working set _060326.pdf

I am uploading a 23-page architectural working drawing set
for the Disrupt building.

Your task is to transform these architectural working drawings
into a highly accurate, professional, enterprise-level 3D
architectural visualization and building massing model.

This is NOT a conceptual redesign.

This is an ARCHITECTURAL RECONSTRUCTION AND VISUALIZATION
TASK based on the provided working drawings.

Your highest priority is:

1. Architectural accuracy
2. Dimensional consistency
3. Correct building proportions
4. Correct floor relationships
5. Correct facade and opening placement
6. Professional-quality 3D output
7. Clear documentation of uncertainties

Do not rush directly into generating an attractive image.

First understand the building completely.

=====
PHASE 1 — COMPLETE DRAWING ANALYSIS
=====

Read and analyze ALL 23 PAGES individually.

Do not skip pages because they appear repetitive or contain
technical drawings.

Create a structured architectural analysis report.

Identify and document:

A. PROJECT IDENTIFICATION

- Project name
- Client
- Architectural consultant
- Structural consultant
- Drawing set title
- Drawing numbers
- Drawing revisions and dates, if visible
- Any project information visible in title blocks

B. FLOOR PLANS

Analyze each floor separately:

GROUND FLOOR:

- Overall building footprint
- External wall arrangement
- Internal room layout
- Room names and functions
- Entrance and exit locations
- Main circulation routes
- Staircases
- Voids and double-height areas
- Courtyards or open spaces
- Toilets and service spaces
- Door locations
- Window locations
- Any visible structural elements
- Any special architectural features

FIRST FLOOR:

Perform the same analysis.

SECOND FLOOR:

Perform the same analysis.

For every floor, identify how it connects vertically to the other floors.

C. DIMENSIONS AND SCALE

Identify every readable critical dimension.

Determine the dimensional units **ONLY** from the drawings or reliable drawing information.

Do **NOT** assume dimensions are in millimetres, metres, feet, or inches without evidence.

If the units cannot be established:

- State that clearly.
- Identify the affected dimensions.
- Request clarification where necessary.

Prioritize verification of:

- Overall building length and width
- Floor-to-floor heights
- Ceiling heights, where shown
- Wall thicknesses
- Door widths and heights
- Window widths and heights
- Stair dimensions
- Major room dimensions
- Parapet heights
- Roof levels
- External projections

Important:

The drawing notes indicate that the drawings should not be scaled and that stated dimensions must be used.

Never estimate dimensions from the visual size of a scanned drawing when a stated dimension is available.

D. ELEVATIONS

Analyze all four elevations:

PAGE 15 — FRONT ELEVATION (A-201)

PAGE 16 — LEFT ELEVATION (A-202)

PAGE 17 — RIGHT ELEVATION (A-203)

PAGE 18 — BACK ELEVATION (A-204)

For each elevation, identify:

- Overall building height
- Number of visible levels
- Floor slab lines
- Parapets
- Roof configuration
- Window arrangement
- Door arrangement
- External wall finishes
- Vertical and horizontal architectural features
- Projections and recesses
- Screens, louvers, shading devices
- Balconies or terraces, if shown
- Any visible architectural details
- Alignment with the floor plans

Do not invent architectural features.

If an elevation conflicts with a floor plan:

- Identify the exact conflict.
- Reference the relevant page numbers.
- Explain what needs clarification.

- Do not silently choose one version.

E. SECTIONS

Analyze:

PAGE 19 — SECTION A-A (A-301)

PAGE 20 — SECTION B-B (A-302)

Extract and document:

- Floor-to-floor heights
- Finished floor levels
- Slab thicknesses, where shown
- Ceiling heights
- Roof and parapet heights
- Vertical circulation
- Building section profile
- Major structural and architectural relationships
- Any double-height spaces
- Any critical level differences

Use the sections to validate the 3D building height.

Do not create building heights based only on visual estimation from elevations.

F. DOOR, WINDOW & SHADING DETAILS

Analyze:

PAGE 21 — A-601 (GROUND FLOOR)

PAGE 22 — A-602 (FIRST FLOOR)

PAGE 23 — A-603 (SECOND FLOOR)

Identify:

- Door types
- Window types
- Door/window sizes, if readable
- Shading details
- Repeated architectural components
- Any special facade systems
- Any details affecting the 3D exterior model

Explain how these details should be incorporated into the building visualization.

=====

PHASE 2 — DRAWING COORDINATION & ACCURACY CONTROL

=====

Before creating the 3D model, prepare a COORDINATION MATRIX.

Cross-check the following:

1. Ground floor plan vs front elevation
2. First floor plan vs front elevation
3. Second floor plan vs front elevation
4. All floor plans vs left elevation
5. All floor plans vs right elevation
6. All floor plans vs back elevation
7. Floor plans vs sections
8. Floor plans vs door/window details
9. Floor levels vs section heights
10. Window and door positions across all relevant drawings

Create a list of:

- Confirmed information
- Unclear information
- Conflicting information
- Missing information
- Assumptions that would be required

DO NOT make silent assumptions.

If a missing detail has no significant effect on geometry, you may propose a clearly labelled provisional assumption.

If it materially affects the building's shape, facade, height, or proportions, ask me for clarification before modelling it.

=====

PHASE 3 — BUILDING GEOMETRY & 3D MODEL

=====

After completing the analysis and resolving critical uncertainties, create the 3D building model.

The model must follow the working drawings, not generic architectural design conventions.

REQUIRED GEOMETRY:

- Accurate overall building massing
- Correct floor slab elevations
- Correct wall thicknesses wherever specified
- Correct roof/parapet geometry
- Correct door and window openings
- Correct stair and void locations
- Correct major projections and recesses
- Correct alignment between floors
- Correct facade proportions
- Correct relationship between internal and external spaces

Every visible architectural opening should be based on the working drawings.

Do not add:

- Decorative windows
- Unspecified balconies
- Unspecified roof structures
- Invented columns
- Invented facade ornaments
- Unspecified landscaping
- Unspecified architectural features

If something is not shown, do not automatically invent it.

For geometry that cannot be verified, maintain a clearly documented assumption rather than presenting it as confirmed.

=====

PHASE 4 — EXTERIOR MATERIALS & DESIGN INTERPRETATION

=====

Analyze the drawings to determine the architectural language and materials that can reasonably be identified.

Identify, where supported:

- Concrete
- Plaster/render
- Brick
- Stone
- Metal
- Glass
- Timber
- Paint finishes
- Shading elements
- Roof materials

Do not arbitrarily assign expensive or decorative materials just to make the render look attractive.

If materials are not specified or cannot be identified:

- Clearly state that.
- Provide a neutral, professional material interpretation.
- Label it as a visualization assumption.
- Preserve the original architectural design.

The final building should look like a realistic professional architectural visualization, not a generic AI-generated house.

=====

PHASE 5 — PHOTOREALISTIC 3D EXTERIOR RENDERS

=====

Create professional-quality exterior visualization views.

REQUIRED VIEWS:

VIEW 1 — FRONT ELEVATION

- Camera aligned with the front facade
- Architectural proportions preserved
- Straight, controlled perspective
- All facade openings clearly visible
- Professional daylight lighting

VIEW 2 — REAR ELEVATION

- Camera aligned with the back facade
- Accurate rear openings and geometry
- Same material and construction logic

VIEW 3 — LEFT SIDE

- Show left-side facade
- Preserve window and wall placement

VIEW 4 — RIGHT SIDE

- Show right-side facade
- Preserve window and wall placement

VIEW 5 — THREE-QUARTER AERIAL VIEW

- Show the overall building massing
- Reveal the relationship between floors
- Show roof configuration
- Professional architectural visualization camera
- Do not use an angle that hides critical architectural elements

VIEW 6 — EYE-LEVEL ARCHITECTURAL VIEW

- Professional human-scale camera
- Show the primary approach and entrance
- Realistic lighting and material response

VISUAL QUALITY:

Aim for a professional architectural visualization standard.

Use:

- Physically plausible lighting
- Realistic material textures
- Correct scale relationships
- Natural shadows
- Accurate reflections
- Realistic glass
- Clean geometry
- Controlled exposure
- Professional camera composition
- High-resolution output where supported

Avoid:

- Overly dramatic cinematic effects
- Excessive fog
- Unrealistic lighting
- Distorted perspectives

- AI-generated architectural artifacts
- Random furniture or people that obscure the building
- Invented design features

Keep the immediate building surroundings minimal and neutral unless the drawings provide site context.

PHASE 6 — 3D ISOMETRIC & CUTAWAY VISUALIZATION

Create a white-model architectural 3D isometric view.

REQUIREMENTS:

- Show the complete building massing
- Show floor-to-floor relationships
- Clearly communicate the internal layout
- Use a cutaway or sectional axonometric where appropriate
- Preserve the actual floor plan geometry
- Show stairs and major circulation
- Show important voids and double-height areas
- Avoid hiding critical spaces unnecessarily

Create, where feasible:

1. Complete exterior massing axonometric
2. Ground floor cutaway
3. First floor cutaway
4. Second floor cutaway
5. Exploded floor-by-floor view

The isometric should be an architectural communication tool, not an artistic reinterpretation.

PHASE 7 — MODEL STRUCTURE & DIGITAL OUTPUT

If you can generate a real 3D model, prioritize that over a single AI-generated image.

Preferred formats:

- GLB / glTF
- OBJ
- Blender-compatible model
- Three.js-compatible geometry

The model should ideally contain separate logical components:

- Ground floor
- First floor
- Second floor
- Walls

- Slabs
- Roof
- Doors
- Windows
- Stairs
- Major architectural elements

If direct 3D model export is not supported, provide:

- A. A detailed building geometry specification
- B. A complete Three.js massing implementation, if feasible
- C. A suitable Blender modelling workflow
- D. A detailed prompt for D5 Render or another suitable architectural visualization tool

Do not claim to have generated a downloadable 3D model unless you have actually generated the file.

=====

PHASE 8 — HIGH-QUALITY RENDERING PROMPT

=====

After completing the architectural analysis, write a detailed production-ready prompt for photorealistic rendering.

The prompt must be specific to THIS building.

Include:

- Building geometry
- Number of floors
- Architectural style, only as supported by the drawings
- Facade materials
- Window configuration
- Roof configuration
- Lighting
- Camera angle
- Lens and perspective guidance
- Material realism
- Architectural accuracy requirements
- Negative prompts for common AI errors

Do not write a generic prompt such as:

"Create a beautiful modern building."

Write a prompt that can be used in:

- Midjourney
- D5 Render
- Blender
- Other architectural visualization workflows

=====

PHASE 9 — QUALITY ASSURANCE REPORT

=====

Before finalizing the work, conduct a quality review.

Check:

- ☐ All 23 pages reviewed
- ☐ All floor plans analyzed
- ☐ All four elevations analyzed
- ☐ Both sections analyzed
- ☐ Door/window details analyzed
- ☐ Dimensions verified where readable
- ☐ Units confirmed or flagged
- ☐ Floor heights cross-checked
- ☐ Facade openings cross-checked
- ☐ Roof geometry verified
- ☐ Major architectural features preserved
- ☐ No unverified features presented as confirmed
- ☐ Conflicts documented
- ☐ Assumptions documented
- ☐ 3D model proportions checked
- ☐ Render views reviewed for architectural distortion

Provide a FINAL ARCHITECTURAL VALIDATION REPORT.

Clearly separate:

1. Confirmed drawing information
2. Modelled geometry
3. Visualization assumptions
4. Unresolved uncertainties
5. Items requiring architectural clarification

=====

WORKFLOW INSTRUCTION

=====

START WITH PHASE 1 ONLY.

First provide the complete architectural analysis of all 23 pages.

Do not immediately jump to a generic exterior render.

After the analysis:

- Identify the critical uncertainties.
- Ask only the necessary clarification questions.
- Then proceed to accurate 3D massing and visualization once the essential information is resolved.

The goal is an accurate, professional, high-resolution architectural visualization of the actual Disrupt building shown in the uploaded working drawings.

Accuracy is more important than visual decoration.