

Disrupt 141-C — Full Project Report

Phase 1 drawing analysis + Phases 2-9 reconstruction record

Prepared from the 23-sheet architectural working set `Disrupt\_Architectural Working set \_060326.pdf`
(Ingenious Design Studio, February 2026). Client: Disrupt. Structural consultant: Almuhandis.

PART 1 — DRAWING ANALYSIS

1.1 Scope and method

All 23 sheets were read individually at full resolution; elevations, sections and dimension plans were re-rendered at 400–500 dpi and cropped so level tags and dimension strings could be read as written.

The set is **not** a new-build design. It is a refurbishment and fit-out package for an existing three-storey building, drawn over a survey. Every plan legend distinguishes existing wall, proposed extension wall, demolish-or-reduce beam drops, proposed beam drops, existing column, proposed column.

The set contains ****no site plan, no roof plan, no structural grid, no finishes schedule and no overall building envelope dimension.****

1.2 Project identification

Item	Value
Client	DISRUPT
Architectural consultant	Ingenious Design Studio (architecture / interiors / furniture)
Structural consultant	ALMUHANDIS — hafiztafseer@yahoo.com, 0336-2064652
Designed / checked / approved	Faizan Fazal
Drawn	Abu Huraira
Date on every title block	February 2026
Scale on every title block	**NTS**
Revision	Blank on all 23 sheets — Revision 0
Building reference	141-C (prayer area labelled "Block D"; door schedules Zone C / Zone D)
PDF distilled	6 March 2026

1.3 Drawing register

| PDF page | Sheet | Title as drawn | Notes |

1	---	---	---	---
1	—	Cover	Client and consultant only	
2	A-000	List of architectural working drawings	Register, tag legend, 8 general notes	
3	A-101	Ground floor key plan		
4	A-102	First floor key plan		
5	A-103	Second floor key plan		
6	A-111	Ground floor dimension & demolition plan	Primary dimensional source	
7	A-112	First floor dimension & demolition plan	Primary dimensional source	
8	A-113	Second floor dimension & demolition plan	Primary dimensional source	
9	A-401	Ground floor furniture plan		
10	A-402	First floor furniture plan		
11	A-403	Second floor furniture plan		
12	A-501	Ground floor reflected ceiling plan		
13	A-502	First floor reflected ceiling plan		
14	A-503	Second floor reflected ceiling plan		
15	A-201	Front elevation		
16	A-202	Rear elevation	Register calls it "Left elevation"	
17	A-203	Left side elevation	Register calls it "Right elevation"	
18	A-204	Right side elevation	Register calls it "Back elevation"	
19	A-301	Section A-A	Register numbers it "5-301"	
20	A-302	Section B-B		
21	A-401	Ground floor Zone C door window schedules	Number clashes with furniture plan; register says A-601	
22	A-402(A)	First floor Zone D door schedules	Register says A-602	
23	A-403	Second floor Zone C door schedules	Number clashes; register says A-603	

1.4 Units, scale and dimensional basis

Units are feet and inches, stated explicitly. Every dimension carries foot and inch marks (20'-3"x14'-9", 3'-6", 5¾", ±0'-0"). No inference required.

The set cannot be scaled. General note 1 on A-000: "This drawing is not to be scaled, stated dimensions are only to be considered." Independently, every title block reads NTS. General note 2 requires site verification of all dimensions.

Calibration used for the reconstruction: 41.70 pixels per foot at 500 dpi ($\approx 1" = 12'-0"$), verified against three stated dimensions on three different sheets:

	Stated dimension	Sheet	Measured px	Implied px/ft
---	---	---	---	---
36'-0" (gym)	A-111	1499	41.64	
52'-2" (workstation bay)	A-112	2179	41.77	
8'-0" (courtyard tree circle)	A-111	334	41.75	

Agreement better than 0.5%. Independent check: courtyard measured 22.7' × 28.0' off the drawing against a stated 23'-0" × 28'-4" (1.3%).

Overall building length and width are not stated anywhere in the set. Derived envelope:
compound $\approx 151' \times 130'$; building $\approx 148' \times 127'-6''$.

1.5 The vertical datum — the most reliable data in the set

The level ladder is drawn identically on all four elevations and both sections and agrees exactly.

Floor-to-floor is a constant 11'-5" on all three storeys.

Level	Elevation	Derivation
---	---	---
Road level	$\pm 0'-0''$	Datum
Plinth / ground FFL	$+1'-0''$	1'-0" above road
Ground floor lintel	$+11'-4''$	
Ground structural slab	$+12'-2''$	
First FFL	$+12'-5''$	$+11'-5''$
First floor lintel	$+22'-7''$	
First structural slab	$+23'-7''$	
Second FFL	$+23'-10''$	$+11'-5''$
Second floor lintel	$+34'-0''$	
Roof structural slab	$+35'-0''$	
Roof level (top of slab)	$+35'-3''$	$+11'-5''$
Parapet	$+39'-3''$	4'-0" above roof

Section A-A confirms: **10'-8" clear** floor to slab soffit, **10'-2" clear** under beams, **6" slab**, **9" beam drop**. Stair: **5¾" riser**, **1'-0" tread**.

Local clear heights noted in red: 10'-8" (gym, wide passage, meeting room, reading room, procurement store); 12'-8" (first floor workstations); 17'-0" (ground floor reading room and meeting room); 6'-0" under the stair landing.

Levels off the main datum — real steps, not drafting noise:

- Courtyard at **+0'-6"**
- West wing ground floor at **+2'-0"** (reduced clear heights 10'-10", 11'-1", 11'-6")
- West wing first floor at **+13'-11"** and **+16'-11"** (the +16'-11" pocket has only 7'-10" headroom)
- West wing second floor at **+25'-9"** (other bays read +28'-6", +29'-6")

1.6 Ground floor (A-101 / A-111 / A-401 / A-501)

Deep courtyard building filling a walled compound, front on the south edge, green lawn in the south-west corner. Organised around a central open courtyard with a circular tree planter.

Entrance sequence: guard post 6'-0"x6'-0" → entrance foyer 19'-0"x8'-11" → reception 20'-6"x21'-5"

→ courtyard. Lawn 30'-6"x19'-0" to one side.

Circulation: 4'-6" passage north-south past the courtyard; 13'-4" passage east-west at +1'-0"; 5'-9" passage at +0'-4" bridging the courtyard; 5'-0" corridors in the west wing; 4'-11" corridor; 6'-9" passage to the board room; 4'-0" service passages north-east. Stairs north-central with 6'-0" clear under the landing.

West wing at +2'-0": workstations 15'-1"x19'-8", 15'-10"x22'-8", 16'-1"x13'-11", 24'-9"x11'-4", 15'-3"x14'-10", 11'-6"x15'-7", 11'-6"x26'-11", 11'-4"x15'-3", 8'-7"x13'-5"; huddle hubs 19'-7"x11'-10" and 8'-0"x13'-5"; offices 6'-9"x10'-1", 6'-5"x13'-10"; lobbies 8'-1"x6'-9", 11'-6"x6'-3"; executive bath 10'-1"x5'-0"; male toilet 17'-9"x16'-7".

North-west: courtyard 16'-3"x8'-3", janitorial 6'-6"x6'-0", female toilet 7'-0"x10'-4", female staff common room / prayer area 18'-2"x15'-0", day care 20'-3"x14'-9", medical assist 19'-4"x8'-4", refreshment area with vending and tea counter.

North-east (staff welfare and plant): gym 36'-0"x19'-11" at +1'-0" with 10'-8" clear; gym store 5'-0"x9'-3"; water pumps and tools 11'-0"x9'-3" over an underground water tank; sitting 11'-0"x10'-2"; gaming room 11'-9"x14'-10"; shower and changing 18'-7"x14'-9" (3 showers, 3 changing); admin dining / rest 13'-2"x14'-9"; generator room 21'-7"x13'-11"; gen store 13'-3"x5'-6".

East (core and support): reading room 20'-7"x19'-4" (17'-0" clear); meeting room 20'-7"x14'-0" (17'-0" clear); UPS room 13'-0"x6'-3"; CCTV room 13'-0"x8'-11"; workshop 18'-8"x7'-9"; procurement store 18'-10"x15'-6"; procurement office 13'-2"x8'-11"; admin offices 13'-2"x8'-10" and 11'-4"x10'-0"; admin check in/out 13'-8"x8'-6"; board room 23'-6"x18'-0"; visitor/executive 11'-0"x5'-1".

South-east edge: area marked "open to sky" with a store alongside.

Emergency exits marked in red at four points on the west and north perimeter.

1.7 First floor (A-102 / A-112 / A-402 / A-502)

Predominantly open-plan workstations with meeting rooms and huddles around the edge.

It does not sit on one level — main floor +12'-5", west block steps to +13'-11" and +16'-11", stair landing marked as a stay level 9'-4"x8'-8".

Voids: "courtyard below 23'-0"x28'-8"" and "double height reception area" cut out of this slab. Section A-A dimensions the reception volume at **22'-1"** and the glazed courtyard walls at **34'-0"** and **33'-6"**.

Work stations 52'-2"x19'-5" for 38 persons (12'-8" clear), 19'-4"x14'-11", 16'-5"x15'-10",

17'-7"x28'-7", 16'-2"x7'-7", 15'-9"x12'-4", 19'-8"x13'-6", 24'-5"x13'-6", 18'-3"x13'-1", 11'-3"x15'-5", 7'-9"x15'-11", 14'-11"x28'-10", 18'-2"x25'-7", 19'-6"x23'-8", 13'-5"x15'-8", 18'-3"x19'-2"; meeting rooms 8'-5"x9'-9", 9'-0"x9'-9", 9'-0"x9'-2", 8'-0"x9'-3", 11'-6"x11'-9" and three at 7'-9"x11'-6"; a room noted "follow existing layout for IT room 16'-6"x16'-0""; male bath 18'-10"x15'-6"; female bath 11'-10"x13'-11"; server room 11'-4"x15'-7".

Circulation: 10'-1", 13'-0", 7'-4", 4'-10", 3'-5" wide passages; 6'-3" corridor. Main stair arrives with 6'-0" clear under the landing. Fire exit at the west end. Green area with shade on the north, green area at the west, back side door at the north-east, generator area outside the line on the east.

1.8 Second floor and roof (A-103 / A-113 / A-403 / A-503)

West half continues as workstations. East half is a **rooftop cafeteria 24'-1"x53'-1" seating 70**,

with bar counters, three store rooms (12'-3"x17'-5", 12'-3"x12'-2", 12'-3"x16'-4"). Between them a

recreational area 27'-2"x19'-2", an **open handwash 15'-1"x8'-1"**, and a ****masjid / prayer area**

(Block D)** with ablution 7'-6"x13'-3" and shoe rack 11'-6"x12'-6".

Main floor +23'-10", west block +25'-9". Work stations 48'-0"x20'-1" (32 persons), 19'-9"x26'-6"

(20 persons), 26'-11"x15'-10", 29'-6"x13'-10" (19 persons), 18'-1"x15'-10", 16'-3"x14'-7", 18'-11"x16'-7", 12'-0"x13'-11"; meeting rooms 8'-9"x10'-0", 8'-4"x10'-0"; female bath 13'-2"x12'-10";

male bath 13'-2"x17'-5"; service stairs on the east edge 13'-6"x16'-0".

Skylight 11'-7"x6'-2" over the stair core. Courtyard void continues as 23'-0"x28'-10".

Roof is not uniform. Both sections tag "**asbestos sheet**" at **+35'-3"** in three locations — A-301 over the passage and over the masjid, A-302 in three bays — drawn with a corrugated profile.

The drawings do not delineate where sheet stops and slab starts. **There is no roof plan in the set.**

1.9 Vertical circulation

1. **Main stair, north-central** — dog-leg, 5¾" riser, 1'-0" tread, 6'-0" clear under the landing.
2. **West block stair** — serves the split levels; stay level 9'-4"x8'-8".
3. **Service stairs, east edge** — 13'-6"x16'-0", drawn externally on A-201 with 3'-6" flights, 5'-9" landings, 3'-0" handrail.
4. **Spiral / curved stair** at the south-east corner of the ground floor.

No lift is shown anywhere in the set.

1.10 Elevations

All four share the same level ladder and the same language: flat rendered wall planes, punched rectangular openings with plain surrounds, no cornices, no string courses, no balconies, no louvres, no shading devices, no visible external structure.

- **A-201 Front** — three storeys, stepped skyline, left end steps down to a one-storey element roofed at +12'-5". Second floor: five punched windows in a slightly recessed plane. First floor: one wide window, two narrow slots, one narrow slot, one square window. Ground floor: single-leaf door, four large windows, wide multi-panel glazed entrance assembly, further windows right. Right end is the external service stair.
- **A-202 Rear** — largely blank wall; left two-thirds unfenestrated across all three storeys. Right third steps and carries five openings. Almost certainly abuts a neighbour.
- **A-203 Left side** — blank wall over a single door at +1'-0"; single-storey element roofed at +12'-5" in the middle; glazed double doors onto that roof, two narrow slots, two square windows, one tall window. Hatched boundary-wall piers close both ends.
- **A-204 Right side** — the service face: continuous row of **eight single and double leaf doors** at ground level matching the east service rooms, with **eight punched windows** at first floor above. Second floor plane blank.

Nothing in any elevation states a material, finish, colour or glazing specification.

1.11 Sections

A-301 Section A-A cuts east-west from the gym through the stair core, courtyard, reception, entrance foyer to the guard post. Establishes: the 11'-5" stack; dog-leg stairs; **courtyard at +0'-6" open to sky with glazed walls 34'-0" and 33'-6"; reception volume 22'-1" high** (double height, not triple); **entrance foyer roofed at +12'-5"**, guard at +1'-0", both single storey; **masjid at +23'-10" with asbestos sheet roof at +35'-3"**.

A-302 Section B-B cuts through the west workstation blocks, day care, wide lobby, green area, female bath, recreational area, male bath. Confirms the same grid and adds the west block levels (+2'-0", +12'-5", +13'-11", +23'-10", +28'-6" on one cut) — the clearest evidence of the stepped datum. Shows asbestos sheet at +35'-3" in three bays.

Neither section shows foundations, plinth beam schedule or roof build-up.

1.12 Door, window and glazing schedules

Every door is 8'-0" high; every window and glazed panel is 7'-0" high on a 1'-0" sill upstand.

Handle height 3'-3". Frame sections 2" with 1'-8" side panels on glazed types.

Ground floor, Zone C (sheet 21) — 30 doors, 4 windows

Mark	Size	Qty	Type and location
---	---	---	---
SDF	16'-0"x8'-0"	1	Sliding door with fixed glass panel — reading room
GDW	7'-6"x8'-0"	1	Glass door with fixed glass panel — reading room
DD1	7'-0"x8'-0"	1	Solid double door — procurement store
DD2	6'-0"x8'-0"	1	Solid double door — sitting
DD3	5'-0"x8'-0"	1	Solid double door — entrance foyer
D1	4'-0"x8'-0"	2	Board room, admin check room
D2	3'-6"x8'-0"	7	Game room, changing sh., admin dining, meeting room, workshop, admin office, procurement
D3	3'-0"x8'-0"	9	Water pumps x2, gym store, sitting, gym area, guard/admin bath, UPS room, procurement, visitor executive
PVD	2'-3"x8'-0"	7	PVC — janitorial, changing x3, commode x3
W1	3'-0"x4'-0"	1	Openable window — procurement
FG1	6'-9"x7'-0"	1	Fixed glass panel — passage
FG2	6'-0"x7'-0"	1	Fixed glass panel — passage
FG3	4'-0"x7'-0"	1	Fixed glass panel — passage

First floor, Zone D (sheet 22) — 23 doors, 9 windows

Mark	Size	Qty	Type and location
---	---	---	---
GDW	19'-0"x8'-0"	1	Glass door with fixed glass panel — meeting room
GDW1	9'-6"x8'-0"	2	Glass door with fixed glass panel — meeting rooms
GDW2	7'-0"x8'-0"	4	Glass door with fixed glass panel — huddles
GDW3	6'-0"x8'-0"	4	Glass door with fixed glass panel — huddles
D1	3'-6"x8'-0"	10	Work stations, passage, baths, corridor x2
D2	3'-0"x8'-0"	1	Work stations
PVD	2'-0"x8'-0"	10	PVC — female bath x4, male bath x6
W1	5'-0"x7'-0"	3	Openable window with fixed glass panel — workstations
W2	4'-0"x7'-0"	2	Openable window with fixed glass panel — workstations
W3	3'-0"x7'-0"	4	Openable window — workstations, CB

Second floor, Zone C (sheet 23) — 23 doors, no windows scheduled

Mark	Size	Qty	Type and location
---	---	---	---
GDW1	7'-0"x8'-0"	2	Glass door with fixed glass panel — huddles
DD1	6'-8"x8'-0"	1	Solid double door — cafeteria
DD2	6'-0"x8'-0"	1	Solid double door — cafeteria
D1	4'-0"x8'-0"	2	Stores
D2	3'-6"x8'-0"	4	Work stations, stores x2, masjid
D3	3'-0"x8'-0"	3	Meeting room, male bath, female bath
PVD	2'-0"x8'-0"	10	PVC — female bath x4, male bath x6

Note: GDW/GDW1/GDW2/GDW3 are **internal** glazed partitions to meeting rooms and huddles, not facade elements. The only facade glazing of scale is the ground floor SDF sliding assembly (16'-0" wide) and

the fixed panels FG1-FG3.

1.13 Material evidence

No finishes schedule, no material legend, no specification reference. Only five materials can be named from the drawings:

Material	Evidence
Reinforced concrete	Slabs, beams, columns, plinth drawn solid grey in both sections; 6" slab, 9" beam dimensioned
Masonry	Cross-hatched wall poché in both sections and in the plan legend
Corrugated asbestos cement sheet	Written "ASBESTOS SHEET" at +35'-3" in three places, drawn with corrugated profile
Glass	Blue glazing hatch on every window, door and fixed panel
PVC	Door type PVD called "PVC door" on all three schedules

Not stated anywhere: external wall finish, render/plaster type, paint colour, cladding, roof waterproofing, floor finishes, glazing tint, frame material, handrail material, parapet coping.

△ Asbestos cement sheet is drawn as existing roofing. Confirm with the consultant before any physical work touches it.

1.14 Conflicts found

#	Conflict	Where	Effect
1	Parapet tagged **+38'-3"** in the body of the front elevation but **+39'-3"** in its own ladder and on A-202/A-203	A-201 vs A-201 ladder, A-202, A-203	1'-0" of parapet on the principal facade
2	Register names A-202 Left, A-203 Right, A-204 Back; sheets are titled Rear, Left Side, Right Side	A-000 vs sheets	Orientation references
3	Door schedules numbered A-601/602/603 in register but A-401/402(A)/403 on sheets; A-401 and A-403 used twice	A-000 vs sheets 21-23	Document control
4	Section A-A listed as "5-301"	A-000	Typo
5	Courtyard 23'-0"x**28'-4"** (GF) vs **28'-8"** (FF) vs **28'-10"** (SF)	A-111/112/113	6" of full-height glazed void
6	West wing levels annotated "from courtyard level" while all others are from road datum	A-112, A-113	Whole west block could shift 6"
7	**Scheduled openings do not reconcile with elevation openings** — 13 windows scheduled, elevations draw many more	Sheets 21-23 vs A-201-204	Every facade opening
8	**Extent of asbestos sheet vs RCC slab undefined** — both at +35'-3", boundary not drawn in plan	A-301, A-302, no roof plan	The roofscape

PART 2 — RECONSTRUCTION RECORD (PARTS A-G)

PART A — Final coordination decisions

A. Front parapet: +38'-3" or +39'-3"

Decision: +39'-3" everywhere. Three independent sources say +39'-3" — the level ladder on A-201

itself, the body tag on A-202, and the body tag on A-203. Only the body tags on A-201 say +38'-3".

The ladder is controlling: it is dimensioned (4'-0" above roof at +35'-3"), identical on all four elevation sheets, and agrees with both sections. One tag against five agreeing sources is a tag error.

B. Courtyard: 28'-4", 28'-8" or 28'-10"

Decision: 23'-0" × 28'-4", the ground floor value. Measured wall-to-wall off A-111 the drawn

courtyard is 22.7' × 28.0', matching the ground floor tag within line weight. Ground floor is also where the courtyard is a real floor rather than a void label. Modelled as one constant void from +0'-6" to open sky, glazed wall 34'-0" high per A-301.

C. West wing levels and "from courtyard level"

Decision: read as absolute levels from road datum. +13'-11" and +16'-11" sit 1'-6" and 4'-6"

above the main first floor; +25'-9" sits 1'-11" above the main second floor — plausible internal steps. Read from the courtyard at +0'-6" instead, the +16'-11" pocket's 7'-10" headroom would conflict with the slab above. Section B-B shows the west workstations at +2'-0", +12'-5", +13'-11",

+23'-10" and +28'-6" on one cut, all from the same datum as the rest of the section. **Five distinct

floor datums modelled.**

D. Schedules versus elevation openings

Decision: elevations govern external openings; schedules govern types and sizes. 58 distinct

openings detected across the four elevations, 96 glazing panels placed. The scheduled glazed types

(GDW families) are named against meeting rooms, huddles, bathrooms and stores — **internal** partitions — so they were not modelled as external openings.

Independent confirmation: first floor openings return $z = 13.36'-20.42'$ from the elevations, against

a predicted 13.42'-20.42' from the stated 12'-5" FFL + 1'-0" sill + 7'-0" pane. **0.06 ft agreement.**

E. Asbestos sheet roof versus RCC slab

Decision: RCC slab everywhere at +35'-3", with corrugated sheet modelled over the east zone only

(X 95'-151', Y 8'-95', matching the masjid / recreational area / rooftop cafeteria on A-113). The sheet sits on the slab rather than replacing it — the conservative reading, so no structure is removed

on the strength of an undrawn boundary.

F. Document control (not geometry)

Raise with Ingenious Design Studio: elevation names one sheet out of step in the register; door schedules A-601/602/603 vs A-401/402(A)/403 colliding with the furniture plans; Section A-A listed as

5-301. The model follows the sheet titles, not the register.

PART B — The 3D model

Files: `Disrupt\_141C.glb` (binary glTF, named hierarchy), `Disrupt\_141C.obj`, plus the full procedural pipeline in `06\_pipeline`.

Coordinate system: feet, **Z-up**, origin at the south-west corner of the compound.

X east 0-151.08', Y north 0-129.98', Z above road datum. Building occupies X 0-148', Y 2-129.5'.

26 named objects:

Group	Objects
Ground floor	`GF\_Slab`, `GF\_External\_Walls`, `GF\_Glazing`, `GF\_Internal\_Walls`, `GF\_Stairs`
First floor	`FF\_Slab`, `FF\_External\_Walls`, `FF\_Glazing`, `FF\_Internal\_Walls`, `FF\_Stairs`
Second floor	`SF\_Slab`, `SF\_External\_Walls`, `SF\_Glazing`, `SF\_Internal\_Walls`, `SF\_Stairs`
Roofs	`Roof\_Level\_12-5\_Slab`, `Roof\_Level\_23-10\_Slab`, `Roof\_Level\_35-3\_Slab`,
`Roof\_Corrugated\_Sheet`	
Parapets	`Roof\_Level\_12-5\_Parapet`, `Roof\_Level\_23-10\_Parapet`, `Roof\_Level\_35-3\_Parapet`
Courtyard	`Courtyard\_Paving`, `Courtyard\_Glazing`
Site	`Site\_Boundary\_Wall`, `Ground\_Apron`

Total: 49,068 triangles. Gross internal area ≈ 37,600 sq ft (GF 13,830 / FF 12,170 / SF 11,580).

How each element was derived

- **Floor plates** from the reflected ceiling plans (A-501/502/503). The grey ceiling fill is a direct read of enclosed floor area per storey — better than closing wall lines broken by every door. Each

ceiling sheet was registered onto its dimension plan by multi-scale template matching on the shared

wall layer, scoring 0.92 / 0.92 / 0.85. The sheets are plotted at different zooms (1.025, 1.08, 1.08).

- **Walls** from the dimension plans. Existing walls are cyan, new/extension walls solid black; the two

were separated by colour, the black layer filtered by thickness to drop text and dimension lines, and

the union rasterised at 6". Envelope vs partition separated by eroding the floor plate (outer 9" band).

- **Monotonic stack.** Each lower plate is unioned with the one above; upper floors snapped out to the

floor below where within 3'-0". Without this, registration slivers become floating slabs and false

3-ft parapets across the plan. This is the one deliberate simplification, and it errs towards continuous structure.

- **Roof levels follow from the stack:** GF but not FF → +12'-5" (entrance foyer, guard); FF but not

SF → +23'-10"; everywhere else → +35'-3". This produces the stepped skyline from geometry.

- **Openings** detected as rectangles on each elevation, de-duplicated across nested double-line outlines, converted to feet against that sheet's ladder, placed on the outermost wall plane of the

correct storey, and the wall split into up to four solid pieces around each — real voids, not decals.

- **Stairs** as real stepped geometry at 5¾" riser / 1'-0" tread in dog-leg flights with mid-landings: main, west block, external service, and the south-east spiral.

PART C — Exterior renders (1920 × 1200, rendered from the model)

| File | View |

| --- | --- |

| `01\_front\_elevation.png` | Front, near-orthographic (12° lens from 420 ft — verticals parallel, overlays A-201) |

| `02\_front\_three\_quarter.png` | Front three-quarter from the south-west |

| `03\_rear\_three\_quarter.png` | Rear three-quarter — largely blank wall, as A-202 draws it |

| `04\_left\_side.png` | Left (west) side with the mid-level terrace at +12'-5" |

| `05\_right\_side.png` | Right (east) side — the service door row and first floor window rhythm |

| `06\_aerial\_three\_quarter.png` | High aerial — courtyard void, stepped roofscape, spiral stair |

| `07\_eye\_level\_entrance.png` | Eye level at 5'-6" on axis with the entrance foyer |

Lighting: single warm key from the south-west, cool sky fill, soft shadow map, neutral exposure, no

bloom or vignette. Nothing added for visual effect.

Honest artefact: wall edges carry a faint 6" stepping because the plan is rasterised from the drawings at 6" resolution rather than traced as smooth polylines. Re-run the build at a finer cell size if the renders need to go to print.

PART D — Isometric and cutaway

| File | View |

| --- | --- |

| `08\_axonometric\_white.png` | Complete white-model massing |

| `09\_cutaway\_ground.png` | Ground floor cutaway with space labels |

| `10\_cutaway\_first.png` | First floor cutaway — split-level west block, courtyard and reception voids |

| `11\_cutaway\_second.png` | Second floor cutaway — cafeteria, recreational area, masjid, skylight |
| `12\_exploded\_axonometric.png` | Exploded floor-by-floor — ground, first, second, roofs |

Cutaways are driven by layer visibility rather than a clip plane, so stairs belonging to hidden storeys are hidden with them.

PART E — Model specification

Levels used (exactly as stated)

Level	Elevation
Road datum	$\pm 0'-0"$
Ground FFL	$+1'-0"$
West wing ground FFL	$+2'-0"$
Courtyard paving	$+0'-6"$
Ground structural slab	$+12'-2"$
First FFL	$+12'-5"$
West first FFL	$+13'-11"$ and $+16'-11"$
Second FFL	$+23'-10"$
West second FFL	$+25'-9"$
Roof slab	$+35'-3"$
Parapet	$+39'-3"$

Floor-to-floor $11'-5"$ on all three storeys (model measures 11.4167 ft each). Structural slab 6" with
3" screed to finished floor; clear $10'-8"$ to soffit, $10'-2"$ under beams.

Dimensions used

Element	Dimension	Source
Courtyard void	$23'-0" \times 28'-4"$, full height, open to sky	Stated, A-111
Courtyard glazed wall	$34'-0"$ high	Stated, A-301
Reception volume	$20'-6" \times 21'-5"$, $22'-1"$ high	Stated, A-111 / A-301
Entrance foyer	$19'-0" \times 8'-11"$, roofed at $+12'-5"$	Stated
Guard post	$6'-0" \times 6'-0"$, single storey	Stated
Doors	$8'-0"$ high throughout	All three schedules
Windows / glazed panels	$7'-0"$ high on a $1'-0"$ sill	Schedules, confirmed by elevations
Stairs	$5\frac{3}{4}"$ riser, $1'-0"$ tread	Stated, A-301
External wall	9"	Section poché — assumption
Structural slab / beam drop	6" / 9"	Stated, A-301

Materials

Only the five materials named in the drawings are used: RC slabs/beams/columns, masonry walls,
corrugated asbestos cement sheet where tagged, glass, PVC doors. The visualisation reads as

rendered and painted masonry with punched openings. No stone, timber, cladding, curtain wall, louvre, fin, canopy or facade lighting has been added, because none is drawn.

Every assumption

| # | Assumption | Why | Risk if wrong |

| --- | --- | --- | --- |

| 1 | **Overall envelope reconstructed from stated internal dimensions and drawing geometry because no overall perimeter dimension is provided** | Required; none exists in the set | Whole-model scale. Cross-checks agree to 0.5% |

| 2 | Plan scale 41.70 px/ft at 500 dpi (1" = 12'-0") | Verified on three stated dimensions | As above |

| 3 | External wall 9", internal 4½"-9" as drawn | Section poché and normal practice | Areas shift well under 1% |

| 4 | Parapet 4'-0" on main roof, 3'-0" on the two lower terraces | +39'-3" stated for main roof; lower terraces untagged | Skyline of lower elements only |

| 5 | Site boundary wall 8'-0" high | Not dimensioned anywhere | Cosmetic; separate object, can be hidden |

| 6 | Corrugated sheet roof over X 95'-151', Y 8'-95' | Both sections tag it; neither draws the boundary | Roofscape only; slab beneath continuous |

| 7 | West wing zone boundaries at the nearest wall line to each level tag | Tags give levels, not extents | Where the step falls, by a few feet |

| 8 | Upper floors snapped out to the floor below where within 3'-0" | Registration slivers between sheets | Prevents false terraces; real setbacks over 5 ft preserved |

| 9 | Elevation openings mapped proportionally onto the plan envelope | Each elevation drawn at its own scale, no horizontal dimensions | Opening positions along each facade, by a few feet |

| 10 | Building faces south | Entrance, lawn, guard on that edge; A-204 service doors match the east service rooms | Sun angles; facade naming |

| 11 | Neutral render and paint, clear glazing | No finishes schedule | Appearance only |

PART F — Production rendering prompts

Midjourney / image generators

> Architectural visualisation photograph of an existing three-storey courtyard office building in
> Karachi, Pakistan. Plain rendered and painted masonry, warm off-white, flat wall planes with no

> cladding, no cornices, no string courses. Stepped flat roofline with a plain rendered parapet
> standing four feet above the roof. Punched rectangular windows with simple plaster reveals and slim

> aluminium frames, all window panes the same height, sills one foot above each floor line, arranged

> in an irregular rhythm across a long low facade. Ground floor has tall glazed openings and a wide

> multi-panel glazed entrance assembly; the entrance sits under a single-storey flat-roofed element

- > that steps down from the three-storey mass behind. An open external concrete stair with a plain
- > metal handrail sits at the right end of the front facade. A plain boundary wall runs across the
- > foreground. Overcast-to-clear late morning daylight, soft realistic shadows, controlled vertical
- > perspective, full-frame 35mm tilt-shift architectural lens, no distortion, neutral white balance,
- > high dynamic range, clean exposure, no people, no cars, no trees in front of the building.
- > --ar 3:2 --style raw
- >
- > **Negative:** curtain wall, glass tower, louvres, brise-soleil, timber cladding, stone cladding,
- > decorative fins, cantilevered canopies, balconies, curved facades, rooftop plant, solar panels,
- > water tanks, signage, modern parametric forms, dramatic sunset, fog, lens flare, fisheye.

D5 Render / Twinmotion / Lumion

Import `Disrupt\_141C.glb` at 1 unit = 1 foot, Z-up. Then:

- **Materials.** `\*\_External\_Walls`, `\*\_Parapet`: fine exterior render, warm off-white, roughness 0.85, bump 0.02, no tiling pattern. `\*\_Slab`, `Roof\_Level\_\*\_Slab`: smooth off-form concrete, roughness 0.75, mid-grey. `Roof\_Corrugated\_Sheet`: corrugated fibre-cement, weathered grey, profile pitch 3", roughness 0.9. `\*\_Glazing`, `Courtyard\_Glazing`: clear architectural glass, 6 mm, transmission 0.85, reflectance 0.08, very slight green tint, slim dark aluminium frame. `\*\_Stairs`: precast concrete with a plain 3'-0" steel tube handrail. `Ground\_Apron`: neutral grey paving.
- **Sun.** Karachi, 24.86°N 67.01°E. Morning 10:00 (azimuth ~south-east); afternoon 15:30 (~south-west, models the front facade best). Clear sky, light haze.
- **Cameras.** Front three-quarter: 24 mm, eye height 5'-6", two-point with verticals locked, ~120 ft off the south-west corner. Aerial: 35 mm, 260 ft above grade, 40° down, from the south-west so the courtyard reads. Entrance: 35 mm at 5'-6", on axis with the entrance foyer, 70 ft back.
- **Post.** Neutral exposure, no bloom, no vignette, slight contrast curve only. No entourage covering the facade.

Blender

```
import bpy
bpy.ops.import_scene.gltf(filepath="Disrupt_141C.glb")
# model is in feet, Z-up; scale to metres if your scene needs it
for o in bpy.context.selected_objects:
    o.scale = (0.3048, 0.3048, 0.3048)
```

Cycles, 512 samples with denoising. Sun lamp 3° angular diameter, strength 4, rotated to a Karachi

afternoon. Nishita sky, altitude 30°, dust 0.2. Camera 24 mm with lens shift to lock verticals rather than rotating up. Filmic or AgX view transform. Object names carry through the glTF import, so materials can be assigned by name in one pass.

What to tell any tool NOT to do

The building has no curtain wall, no balconies, no louvres, no canopies, no roof plant, no signage and no landscaping beyond the two lawns and the courtyard tree drawn on A-111. Every one of those is a thing these tools add by default. **The window rhythm is irregular and must stay irregular** — regularising it is the single most common way an AI render stops being this building.

PART G — QA report

Check	Result
Ground floor matches A-111	**Pass, by construction** — wall layer rasterised from that sheet
First floor matches A-112	**Pass, by construction**
Second floor matches A-113	**Pass, by construction**
Front facade matches A-201	**Pass with caveat** — 24 openings; horizontal positions proportional
Rear facade matches A-202	**Pass with caveat** — 6 openings, mostly blank wall
Left facade matches A-203	**Pass with caveat** — 11 openings
Right facade matches A-204	**Pass with caveat** — 17 openings, service door row present
Section A-A matches vertical geometry	**Pass** — 11.4167 ft floor-to-floor on all three storeys
Section B-B matches vertical geometry	**Pass** — west split levels present
Courtyard is a true vertical void	**Pass** — 23'-0"×28'-4" from +0'-6" to sky
Reception is double height	**Pass** — 22'-1" volume, void cut through the first floor slab
West wing split levels preserved	**Pass** — +2'-0", +13'-11", +16'-11", +25'-9"
Main stair correctly positioned	**Pass** — north-central core, located from A-111
External service stair correctly positioned	**Pass** — east edge, outside the envelope as A-113 draws it
Ground-floor service doors match right elevation	**Pass** — 8 openings, east facade, ground level
Major facade openings correspond to elevations	**Pass** — 58 distinct openings, 96 glazing panels
Door and window heights correct	**Pass** — 8'-0" doors, 7'-0" panes on 1'-0" sills
Roof levels correct	**Pass** — +12'-5", +23'-10", +35'-3"
Parapet decision documented	**Pass** — Part A item A
Roof sheet vs RCC decision documented	**Pass** — Part A item E
No invented architectural features	**Pass** — nothing modelled that is not drawn, except site wall height
No distorted proportions	**Pass** — vertical exact, horizontal calibrated to 0.5%

What is genuinely verified

The vertical dimension is the strongest part of this model. The level ladder is repeated on six sheets and agrees with itself everywhere; the model reproduces 11'-5" floor-to-floor and 10'-8" clear on all three storeys; and the window heads and sills derived independently from the elevations land within 0.06 ft of what the schedules predict. That cross-check was not built in — it fell out.

Horizontal geometry is **calibrated rather than dimensioned**. Good enough for area take-offs, adjacency checks and visualisation. **Not good enough to order anything from.**

What is not verified, in order of importance

1. **The absolute size of the building.** Everything rests on the calibration. One stated overall dimension converts the whole model from calibrated to dimensioned — a five-minute tape measurement.
2. **Horizontal positions of facade openings.** Right storey, right count, right size; position along each facade is proportional.
3. **The sheet-roof boundary.** Modelled conservatively as an overlay on a continuous slab.
4. **West wing zone boundaries.** Levels stated; extents read from the nearest wall line.
5. **Orientation.** No north point in the set. South-facing is an inference from the entrance, lawn, guard post and east service doors.

Recommended next step

Send Ingenious Design Studio the three document-control items in Part A section F, and ask for **one overall dimension on the front elevation**. With that single number the model becomes dimensioned rather than calibrated, and nothing else has to change — the geometry is procedural, so it re-scales in one run of ``build_model.py``.